

**Does your agency  
adjust pay  
quantities for  
excess concrete  
over beam  
haunches?**

<b>State</b>	<b>Yes</b>	<b>No</b>	<b>Comments</b>
Alabama		X	
Alaska		X	
Connecticut	X		Haunch pay based upon actual field measurements of the girder camber
Florida	X		See Spec 400-22.2.4 Deck Girders and Beam Spans
Georgia		X	Lump sum for superstructure
Illinois		X	
Indiana		X	
Iowa		X	If a plan error occurs
Kansas		X	pay based on theoretical
Kentucky		X	
Maine		X	superstructure concrete paid as a lump sum
Massachusetts		X	
Michigan		X	
Missouri		X	
Nebraska		X	
New Hampshire		X	paid as plan quantity
New Jersey	X		If measured quantity is more than 10% of the contract quantity
North Carolina		X	If a plan error occurs
Ohio		X	incidental to the calculated volume
Oklahoma		X	Haunch estimates included in quantities, any error is resolved via change order
Oklahoma		X	haunch quantity is included in the plan quantity for AA concrete, error resolved by change order.
Oregon		X	Incidental Item
Pennsylvania		X	typically lump sum, but bridge rehabs are line item projects and a 25% overrun gives contractor the right to renegotiate a price.
South Carolina		X	
South Dakota		X	Haunch estimates included in quantities, typically no adjustments in the field for this item
Utah		X	
Virginia	X		pay based on field measurements of the actual haunch depths
Washington		X	
West Virginia	X		