

# FIU PEDESTRIAN BRIDGE COLLAPSE

## AASHTO Committee on Construction VIRTUAL ANNUAL MEETING


Gary J. Klein, P.E., S.E. – Wiss, Janney, Elstner Associates, Inc.

Alan R. Phipps, P.E., S.E. – FIGG Bridge Engineers, Inc.


August 13, 2020

# FIU University City Prosperity Pedestrian Bridge

Location of the signature bridge in red.  
Contractor's adjacent casting yard  
and construction trailers on  
3/26/2017. (Source: NTSB Factual Report)



# Rendering Of Proposed Signature Pedestrian Bridge




SOURCE: NTSB Factual Report




# Location of Main Span

Main span was precast on land parallel to highway. Then, over part of weekend, it is moved into place as one piece and placed on piers






# Moving Main Span Into Place On March 10, 2018



SOURCE: NTSB Factual Report

# Rendering Of Bridge Cross Section

Concrete Truss




Analogous to large concrete beam with struts running along centerline



Typical Precast Concrete I-Beam



# Map Illustrating Nomenclature Of The Diagonal And Vertical Members Of The Bridge Main Span





Project Participants

ON-SITE

OWNER

Florida International University (FIU)

STATE AGENCY SUPPORT

Florida Department of Transportation (FDOT)  
OVERSIGHT OF LOCAL PROJECT

CONSTRUCTION

OWNER'S CONSTRUCTION  
ENGINEERING & INSPECTION

Network Engineering Services, Inc.  
d/b/a Bolton-Perez and Associates (BPA)

CONTRACTOR FOR PROJECT  
DESIGN-BUILD

Munilla Construction  
Management, LLC (MCM)

CONSTRUCTION

MCM

CONCRETE SUBCONTRACTOR

The Structural Group of South Florida, Inc (TSG)

FORMWORK SHORING SUBCONTRACTOR

RC Group, LLC (RCGROUP)

CRANE SUBCONTRACTOR

George's Crane Service (George's Crane)

OTHER SUBCONTRACTORS

POST-TENSIONING SUBCONTRACTOR

Structural Technologies, LLC (Structural or VSL)

BRIDGE MOVE SUBCONTRACTOR

Barnhart Crane and Rigging, Co. (Barnhart)  
with Subcontractors  
Bridge Diagnostics, Inc. (BDI)  
RLT Engineering Solutions, LLC (RLT)

OFF-SITE

DESIGN

DESIGN CONSULTANT /  
ENGINEER OF RECORD (EOR)

FIGG Bridge Engineers, Inc. (FIGG)

Design Management  
Bridge Design  
Submittal reviews at design office  
and occasional site visits during  
construction as requested by MCM

INDEPENDENT PEER REVIEW

The Louis Berger Group, Inc.  
(Louis Berger)

Independent Engineering Analysis  
and review of bridge design



# Roles and Responsibilities - **OFF-SITE**

To Design Project following National & State Codes and Florida Standard Construction Specifications

**FDOT rules: Engineer of Record (EOR) is not permitted to have an inspection role during construction with full time oversight (Safety Recommendation is to change this)**



FLORIDA  
DEPARTMENT  
OF  
TRANSPORTATION



STANDARD SPECIFICATIONS  
FOR  
ROAD AND BRIDGE  
CONSTRUCTION

JULY 2015

**Design Consultant/Engineer  
of Record (EOR)**

**FIGG Bridge Engineers Inc.**

**Design Manager  
Bridge Design**

**Submittal Reviews at design office  
Occasional site visits during  
construction as requested  
by MCM**

**Independent Peer Review**

**The Louis Berger Group  
Letters stated all design  
requirements were met  
Review Plans & Specifications**



# Elements Considered

## Design

- Calculations (WJE)

- Redundancy

## Construction

- Construction of Member 11/12 deck connection (WJE)

- Bridge move

- Communication between construction site and design engineer

- Crack monitoring


- Street closure



# Design

All Aspects of the design by FIGG were the subject of numerous Governmental, Contractor, and Peer Reviews over a 14 month period.

All accepted before construction started



9 Submittals to FDOT for review at 30%, 90%, 100% design plans

32 reviewers - FDOT with 3 outside consultants

Over 340 written comments (electronic review system) resolved to acceptance before release for construction plans issue

37 Reviewers - FIU, FDOT, FHWA, Miami-Dade County

Final design is shown in the approved release for construction (RFC) plans

# RFC PLANS ARE BUILT

# FLORIDA INTERNATIONAL UNIVERSITY AND CITY OF SWEETWATER UNIVERSITY CITY

## R.F.C. SUPERSTRUCTURE PLANS

FINANCIAL PROJECT ID - 434688-1-58-01  
CONTRACT BT-904  
MIAMI-DADE COUNTY  
UNIVERSITY CITY PROSPERITY PROJECT

### INDEX OF PROJECT PLANS

SHEET NO.	SHEET DESCRIPTION
1B-01 THRU 1B-03	LANDSCAPE
1B-04 THRU 1B-06	LANDSCAPE
1D-01 THRU 1D-05	IRRIGATION
1E-01 THRU 1E-10	STRUCTURAL PLANS
1F-01 THRU 1F-10	ROADWAY
1G-01 THRU 1G-05	PROJECT SURVEY CONTROL
1H-01 THRU 1H-05	SIGNING AND PAVEMENT MARKING
1I-01 THRU 1I-05	SIGNALIZATION
1J-01 THRU 1J-05	WALL W-1
1K-01 THRU 1K-05	TEMPORARY CRITICAL WALL
1L-01 THRU 1L-05	MECHANICAL
1M-01 THRU 1M-05	ELECTRICAL
1N-01 THRU 1N-05	PLUMBING

PROJECT LOCATION

LOCATION MAP  
SECTION 5 & 6, TOWNSHIP 25 SOUTH, RANGE 39 EAST  
MIAMI-DADE COUNTY, FLORIDA

END PROJECT  
STA. 37+88.69

BEGIN PROJECT  
STA. 30+17.87

SECTION 5 & 6, TOWNSHIP 25 SOUTH, RANGE 39 EAST  
MIAMI-DADE COUNTY, FLORIDA

GOVERNING STANDARDS AND SPECIFICATIONS: FLORIDA  
DESIGN MANUAL OF STANDARDIZATION, DESIGN STANDARDS  
2012, AND STANDARD SPECIFICATIONS FOR ROAD  
AND BRIDGE CONSTRUCTION DATED 2012, AS AMENDED  
BY CONTRACT DOCUMENTS.

APPROPRIATE DESIGN STANDARDS MODIFICATIONS: 01-01-15

For Design Standards Modification Check on  
"Design Standards" at the following web site:  
<http://www.dot.state.fl.us/design>

PREPARED FOR:

**FIU** FLORIDA INTERNATIONAL UNIVERSITY

PLANS PREPARED BY:

**FIGG**

424 North Calhoun Street  
Tallahassee, Florida 32301  
Tel. (904) 224-7400  
Florida Certificate of Authorization 5678

PROFESSIONAL ENGINEER

W. DENNEY PATRICK  
LICENSE NO. 34332  
STATE OF FLORIDA  
PROFESSIONAL ENGINEER

NOTE: THE SCALE OF THESE PLANS MAY  
HAVE CHANGED DUE TO REPRODUCTION.

KEY SHEET REVISIONS		
DATE	BY	DESCRIPTION

15

1

Sum-It: AASHTO LRFD Load Combination Generator  
Figg Bridge Engineers, Inc.  
User's Load Input  
File Name: Diagonal Loads\_Back Span\_South End Pinned.sum

Page 53 of 59  
9/19/2016  
9:30:27 PM

Limit State: STRENGTH III

TU Uniform Temperature

LF: 0.5

TU1: TU-

TU2: TU+

TU3: TU+Temp. Diff.

DC DL Structural Components & Attachments

LF1: 1.25

LF2: 0.9

DC1: DC

FR Friction

LF: 1

FR1: CR+SH+PT\_EOC

FR2: CR+SH+PT\_D10K

WS Wind Load on Structure

LF: 1.4

WS1: WS\_0 DEG

WS2: WS\_15 DEG

WS3: WS\_30 DEG

WS4: WS\_45 DEG

WS5: WS\_60 DEG

WS6: WS\_-15 DEG

WS7: WS\_-30 DEG

WS8: WS\_-45 DEG

WS9: WS\_-60 DEG

WS10: WS+WUP

DW DL Wearing Surfaces & Utilities

LF1: 1.5

LF2: 0.65

DW1: DW

Calculations  
are not built

Load (Row) Number	User's Load ID	Member ID	Joint ID	Fx (kips)	Fy (kips)	Fz (kips)	Mx (ft*kip)	My (ft*kip)	Mz (ft*kip)
1	CR+SH+PT_D10K	741	727	134.9	0	-1.8	0	27.1	0
2	CR+SH+PT_D10K	741	728	-134.9	0	1.8	0	14.2	0
3	CR+SH+PT_D10K	744	729	-207.1	0	1.5	0	-11.8	0
4	CR+SH+PT_D10K	744	730	207.1	0	-1.5	0	-9.9	0
5	CR+SH+PT_D10K	747	731	139.6	0	13.9	0	-55.7	0
6	CR+SH+PT_D10K	747	732	-139.6	0	-13.9	0	-63.2	0
7	CR+SH+PT_D10K	750	733	-300.6	0	4.3	0	-29.1	0
8	CR+SH+PT_D10K	750	734	300.6	0	-4.3	0	-31.8	0
9	CR+SH+PT_D10K	753	735	208.6	0	19.6	0	-75.9	0
10	CR+SH+PT_D10K	753	736	-208.6	0	-19.6	0	-73.5	0
11	CR+SH+PT_D10K	756	737	-316.8	0	4.9	0	-30.7	0
12	CR+SH+PT_D10K	756	738	316.8	0	-4.9	0	-39.6	0
13	CR+SH+PT_D10K	759	739	208.2	0	19.7	0	-72.5	0
14	CR+SH+PT_D10K	759	740	-208.2	0	-19.7	0	-65.7	0
15	CR+SH+PT_D10K	762	741	-197.9	0	3.5	0	-14.1	0
16	CR+SH+PT_D10K	762	742	197.9	0	-3.5	0	-36.7	0
17	CR+SH+PT_D10K	765	743	168.3	0	13.1	0	-41.7	0
18	CR+SH+PT_D10K	765	744	-168.3	0	-13.1	0	-43.8	0
19	CR+SH+PT_D10K	768	745	49.6	0	2.1	0	-2.5	0
20	CR+SH+PT_D10K	768	746	-49.6	0	-2.1	0	-32.5	0
21	CR+SH+PT_D10K	771	747	4.1	0	28.7	0	-8.9	0
22	CR+SH+PT_D10K	771	748	-4.1	0	-28.7	0	-363.2	-0.1

Release for Construction (RFC) Plans incorporate calculations, comments, constructibility comments, final decisions, etc.



# 1st Page of Approved RFC Plans is General Notes that apply to Entire Set of construction drawings (Standard Industry Practice)

## CONSTRUCTION SPECIFICATIONS:

1. FLORIDA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION 2015.
2. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO) LRFD BRIDGE CONSTRUCTION SPECIFICATIONS, SECOND EDITION, 2004 WITH INTERIMS THROUGH 2006.

## DESIGN SPECIFICATIONS:

1. AMERICAN ASSOCIATION OF STATE HIGHWAY AND TRANSPORTATION OFFICIALS (AASHTO) LRFD BRIDGE DESIGN SPECIFICATIONS SEVENTH EDITION WITH 2015 INTERIMS.
2. FDOT STRUCTURES DESIGN MANUAL, JANUARY 2015.
3. AASHTO LRFD GUIDE SPECIFICATIONS FOR DESIGN OF PEDESTRIAN BRIDGES, SECOND EDITION (2009).
4. CEB-FIP MODEL CODE, FIRST EDITION, 1990, TIME DEPENDENT BEHAVIOR OF CONCRETE, CREEP AND SHRINKAGE.
5. AASHTO/AMERICAN WELDING SOCIETY (AWS) D1.5 BRIDGE WELDING CODE (2005).
6. 28 CODE OF FEDERAL REGULATIONS PART 36, 2010 AMERICANS WITH DISABILITIES ACT (ADA) STANDARDS FOR ACCESSIBLE DESIGN.
7. AASHTO GUIDE FOR THE DEVELOPMENT OF BICYCLE FACILITIES, 1999.
8. BUILDING CODE REQUIREMENTS FOR STRUCTURAL CONCRETE, ACI 318-14.
9. BUILDING CODE REQUIREMENTS FOR MASONRY STRUCTURES, TMS 402-13 CODE.

# FLORIDA DEPARTMENT OF TRANSPORTATION



## STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION

JULY 2015



# Redundancy

Redundancy: "...the capability of a bridge structural system to carry loads after damage to or failure of one or more of its members." (AASHTO)

Types of redundancy (FHWA)

- Internal (member with multiple parallel elements)

- Structural (continuous members, fixed connections)

- Load path (more than two primary load carrying members)

Redundancy considerations not applicable for temporary construction phases

AASHTO Design Code general provision for less redundant bridges is to increase design loads by 5%




# Redundancy

## Redundant features of FIU Pedestrian Bridge




Internal Redundancy






# Redundancy

Common examples of less redundant bridges






# Bridge Move – Twist Exceedances during Main Span Transport



- *FIGG established a 0.5-degree twist limit to control cracking.*
- *However, after the accident it was learned that this limit was exceeded. The full degree of the exceedance is somewhat uncertain due to “spikes” in the rotation and twist readings.*
- *The tilt associated with exceeding the established twist limits caused high stresses in the region. Along with other factors, this stress may have contributed to damage in the region and ultimately to the collapse.*



# Communications – Inaccurate, Misleading and Untimely Information from Construction and Inspection Team On-Site to Designer Off-Site

By contract, FIGG did not have a person on-site except for occasional visits – relied on Contractor for information

No information on cracking after bridge move on March 10 provided to FIGG until late on March 12 – pertained almost exclusively to the north diaphragm

FIGG was unaware that the construction joint had not been roughened or that the twist limit had been exceeded





**FIGG (Designer)**

**On-Site Construction/Inspection**

**FIGG staff at site observe no change from pre-move. Leave site at 12:40pm**



**SAT 3/10**

**Bridge move complete 12:30 pm**

**BPA finds significant change in cracking 3:00pm**

**Member #11 PT bar distressed 4:30pm**

**SW 8TH Street opened to traffic 6:00pm**


**Subcontractor text to coworker:  
"It cracked like hell" 7:08 pm**

**SUN 3/11**

**MON 3/12**

**MCM e-mail to FIGG with 16 photos 4:51pm  
mostly of north diaphragm**







# Lack of Crack Monitoring during Re-Stressing



- *Contrary to FIGG instructions and Structural/VSL Safety Guidelines, no one closely monitored cracks in the north-end diaphragm during re-stressing of Member 11*
- *If closely monitored by MCM, Structural/VSL, BPA or Corradino, increases in crack width could have been readily detected by several means, including use of wood block crack gauges, which were already used at the site.*





# Street Closure – Failure to Close SW 8<sup>th</sup> Street While Investigating

FDOT, FIU, MCM and BPA had the authority (alone or collectively) to close traffic.

MCM opened traffic at 6:00 pm on March 10 despite observed worsening cracking.  
Text at 7:08 pm: "It cracked like hell".

From March 12 through March 14, MCM and BPA had full-time site presence and were monitoring cracking. No actions to close traffic.



# Street Closure – Failure to Close SW 8<sup>th</sup> Street While Investigating

No one at the March 15 meeting the morning of the accident suggested closing SW 8<sup>th</sup> Street.

Subcontractor restressing PT bars in Member #11 only defined the work zone as the north two lanes.





# Preeminent Forensic Structural Engineering Experts

## Wiss, Janney, Elstner Associates, Inc. (WJE)



**Gary J. Klein, P.E., S.E.**  
**Executive Vice President**  
**and Senior Principal**

**Bachelors and Master in Civil Engineering**  
**Professional Engineer in Florida**

Since 1979 Gary has investigated hundreds of structures

I-35W Bridge collapse in Minnesota

State investigation coordinating with NTSB on Final Results

Serves on 6 Technical Committees for American Concrete Institute

Named to prestigious National Academy of Engineering in Washington, D.C.

**"for investigations of National and International infrastructure and conveying knowledge from these investigations to the profession."**

**NTSB investigation of I-35W, Minnesota**





# FIU UNIVERSITY CITY PROSPERITY PEDESTRIAN BRIDGE PROJECT

WJE

***Testing of Full-Size  
Replicas of Failed  
Connection***



# Introduction



## Bridge Description

- Two-span truss; 175 foot main span
- Pylon and stay cables (actually pipes) are architectural features
- Canopy and 32-foot wide deck are post-tensioned
- Most diagonals are posttensioned



# Introduction



*Move of Main Span into Position: March 10, 2018*

# Introduction

---



*Collapse: March 15, 2018*



# Introduction

---

## **Scope of WJE Investigation**

- Evaluation of Failure Pattern
- Structural Analyses
  - Finite Element Analyses
  - Code Evaluation of Failed Deck Connection
- Construction Joint Conditions
- Interface Shear Transfer Testing
- Test-based Evaluation of Deck Connection Failure
- Other Factors

# Introduction

---

## **NTSB Probable Cause**

**Design mistakes by FIGG as to the load and capacity of the Member 11/12 deck connection**




## **WJE Exceptions to NTSB/FHWA Probable Cause**

1. Considering the entire construction joint between member 11/12 and the deck, the design as shown on the contract documents meets the AASHTO Code.
2. If the construction joint were roughened as required by the project specifications, which were reconfirmed by email, the collapse would not have occurred.



# Background



# Background


---

## Timeline

- October 19, 2017 Deck concrete casting
- February 24, 2018 Shoring removal (cracking observed)
- March 10, 2018, 12:30 PM Main span moved into final position
- March 10, 2018, 3:07 PM Very significant widening of cracks observed
- March 15, 2018, 11:49 AM Re-tensioning of member 11
- March 15, 2018, 1:45 PM Main span collapses




# After Shoring Removal and Before Move (February 12-March 9, 2018)







# After Shoring Removal and Before Move (February 12-March 9, 2018)






# After Shoring Removal and Before Move (February 12-March 9, 2018)











# After Shoring Removal: Feb. 24

# On Final Supports: March 12






# After Collapse (March 15, 2018)






# After Collapse (March 15, 2018)






# Code Evaluation of Member 11/12 Deck Connection






# Code Evaluation of Member 11/12 Deck Connection



**WJE Evaluation**




# Code Evaluation of Member 11/12 Deck Connection



Member 11


Member 12

## FHWA Evaluation





# Code Evaluation of Member 11/12 Deck Connection



**WJE Evaluation**



# Code Evaluation of Member 11/12 Deck Connection


AASHTO Code:

$$V_{ni} = cA_{cv} + \mu(A_{vf}f_y + P_c)$$

- *c is the cohesion factor*
- *P<sub>c</sub> is defined as the permanent compressive force*
- *For concrete that is roughened to amplitude of 0.25 inches:*
  - *c = 0.24 ksi; μ = 1.0*
  - *v ≤ 0.25f'<sub>c</sub> ≤ 1.5ksi*
- *For concrete that is not intentionally roughened (but laitance is removed):*
  - *c = 0.075 ksi; μ = 0.6*
  - *v ≤ 0.20f'<sub>c</sub> ≤ 0.8ksi*



# Code Evaluation of Member 11/12 Deck Connection



*Abaqus Finite  
Element Model*

Condition	Calculated Demand (kips)	WJE	FHWA
At time of collapse	Northward force at M11/12 connection	1677	
	Axial compression in member 11	<b>1743</b>	
Factored per AASHTO	Northward force at M11/12 connection	<b>1979</b>	1835*
	Axial compression in member 11	2236	
*Does not include construction live load			




# Code Evaluation of Member 11/12 Deck Connection

Summary of Shear-Friction Resistance			
Factored Northward Force (kips)	Surface Condition	Factored Resistance	Capacity/Demand Ratio (CDR)
1979	Roughened	2150	1.09
	Not Roughened	1157	0.58



# Interface Shear Transfer Testing: Specimens





# Interface Shear Transfer Testing: Construction Joint Condition

---

***400-9.3 Preparations of Surfaces:*** Before depositing new concrete on or against concrete which has hardened, re-tighten the forms.

*Roughen the surface of the **hardened** concrete in a manner that will not leave loosened particles, aggregate, or damaged concrete at the surface.* Thoroughly clean the surface of foreign matter and laitance, and saturate it with water.

# Interface Shear Transfer Testing: Construction Joint Condition

---

***June 13, 2017, 7:48 a.m.– BPA to FIGG and MCM***

*“Please make sure we have FIGG blessing for the construction cold joints treatment...”*

***June 13, 2017, 7:56 a.m.– FIGG to BPA and MCM***

*“We have had previous communications with MCM regarding this topic and the FDOT specifications referenced below was to be followed. Let us know if you have any further questions.”*

***June 13, 2017, 8:04 a.m.– BPA to FIGG***

*“Thank you.”*



# Interface Shear Transfer Testing: Construction Joint Condition

---


***400-9.3 Preparations of Surfaces:*** Before depositing new concrete on or against concrete which has hardened, re-tighten the forms.

*Roughen the surface of the **hardened** concrete in a manner that will not leave loosened particles, aggregate, or damaged concrete at the surface.* Thoroughly clean the surface of foreign matter and laitance, and saturate it with water.



# Interface Shear Transfer Testing: Construction Joint Condition

## FHWA Report on Member 11/12 Joint



***FHWA Conclusion: "The evidence indicates that the failure interface coincides with the original cold joint and that the cold joint was not intentionally roughened."***



# Interface Shear Transfer Testing: Construction Joint Condition



***Photograph and laser scan of WJE Specimen 3 (As-placed)***

# Interface Shear Transfer Testing: Construction Joint Condition



***Surface roughening trials***



***Photograph and laser scan of WJE Specimen 4  
(Roughened)***



# Interface Shear Transfer Testing: Construction Joint Condition

Laser Scan Data: Standard Deviation (mm)	
Deck Specimen 1 (recovered by NTSB from site)	0.76
WJE Specimen 3 (as-placed)	0.94
WJE Specimen 4 (intentionally roughened)	2.16

# Interface Shear Transfer Testing: Pre-Cracking



***Stone-splitting wedge sets being used to create a crack across the construction joint of Specimen 6. Most specimens were pre-cracked.***



# Interface Shear Transfer Testing: Loading and Instrumentation



*Linear displacement transducers across interface*



*University of Illinois Southward-Emery test machine (3 million pounds capacity)*

# Interface Shear Transfer Testing: Results (pre-cracked specimens)

Specimen	Peak Load (Average)	Member 11 Load at Failure	%
Roughened	2,594 kips	1,743 kips	149%
Non-roughened	1,455 kips	1,743 kips	83%





# Interface Shear Transfer Testing: Results



## ***Findings:***

- ***Intentional roughening improved the shear capacity of the cracked interface by a factor of 1.78 compared to the as-placed specimens with a cracked interface.***
- ***If the construction joint were roughened as required by the project specifications, which were reconfirmed by email, the collapse would not have occurred.***

# Conclusions

---

## **WJE Exceptions to NTSB/FHWA Findings**

1. Considering the entire construction joint between member 11/12 and the deck, the design as shown on the contract documents meets the AASHTO Code.
2. If the construction joint were roughened as required by the project specifications, which were reconfirmed by email, the collapse would not have occurred.



# Lessons Learned

---

## AASHTO LRFD Bridge Construction Specifications: Article 8.8.2— Bonding

Unless otherwise specified in the contract documents, horizontal joints may be made without keys, and vertical joints shall be constructed with shear keys. Surfaces of fresh concrete at horizontal construction joints shall be rough floated sufficiently to thoroughly consolidate the surface and intentionally left in a roughened condition....

All construction joints shall be cleaned of surface laitance, curing compound, and other foreign materials before fresh concrete is placed against the surface of the joint. Abrasive blast or other approved methods shall be used to clean horizontal construction joints to the extent that clean aggregate is exposed. All construction joints shall be flushed with water and allowed to dry to a surface dry condition immediately prior to placing concrete.

### ***Consider:***

- *Specifying method for measuring surface roughness where ¼ inch amplitude is specified.*
- *Allowing 1) roughening of plastic concrete (followed by abrasive blast cleaning) or 2) roughening of the hardened concrete in a manner that does not damage surface.*

# Lessons Learned

---

## **For Consideration by the AASHTO Committee on Construction...**

1. Ensure that the Engineer of Record is on-site during construction.
2. Ensure careful inspection of construction joints, including joints between precast beams and cast-in-place decks.
3. Emphasize importance of closing traffic if there is any doubt about safety.



QUESTIONS?

# FIU PEDESTRIAN BRIDGE COLLAPSE

## AASHTO Committee on Construction VIRTUAL ANNUAL MEETING

Gary J. Klein, P.E., S.E. – Wiss, Janney, Elstner Associates, Inc.

Alan R. Phipps, P.E., S.E. – FIGG Bridge Engineers, Inc.

August 13, 2020